

GOVERNMENT OF ODISHA  
PANCHAYAT RAJ AND DRINKING WATER DEPARTMENT  
OFFICE OF THE BLCOK DEVELOPMENT OFFICER, KOMNA  
DIST : NUAPADA

NO. 4193 DA. 27.10.22  
**CORRIGENDUM**

**Tender Call Notice No: KMN 08 to 10/22-23**

Pursuant to Govt. of Odisha, Works Deptt, Office Memorandum No. 5984/W Dt. 27.04.2021 , the cost of tender paper will be Rs.6000/- instead of Rs.6720/- in Column No: 04 (Four) of Tender Call Notice KMN-08/22-23 to 10/22-23 published in earlier and the bill of quantity of said tender are modified as noted below. The date of last day for sale of Tender Paper and receive through Post is extended to **05.11.2022 up to 4.00 PM**. The Tender will be opened on dt. **10.11.2022 at 10.30 AM** on the place specified and other terms & condition is unaltered.

Block Development Officer  
Komna

Memo No. 4194 Date. DA. 27.10.22

Copy to the DIO, NIC , Nuapada for information & necessary action . He is requested to upload the above modified in the district website.

Block Development Officer  
Komna

## GENERAL ABSTRACT

Name of work : Construction of Sub Center Kandetara under Komna Block

Sl No	Name of work	Amount (in Rs.)
1	<i>Kandetara Komna</i>	3
1.	Construction of Sub Center <del>Block</del> under <del>Komna</del> Block (Civil work)	Rs. <u>3256885.00</u> <i>3256885.00</i>
2.	Electrification ( Internal & External ) 10%	Rs. <u>325700.00</u> <i>325700.00</i>
3.	PH ( Internal & External ) 13%	Rs. <u>423416.00</u> <i>423416.00</i>
4.	Branding of Building as per HWC Norm (L.S)	Rs. 8500.00
5.	Dismantling of old Building and throwing of Debris away from the site	Rs. <u>37800.00</u> <i>37800.00</i>
	Total :-	Rs. <u>4146201.00</u> <i>4146201.00</i>
6.	Contingency (1%)	Rs. <u>41462.00</u> <i>41462.00</i>
	Total :-	Rs. <u>4187663.00</u> <i>4187663.00</i>
7.	CGST & SGST <del>12%</del> @ 15%	Rs. <u>430400.00</u> <i>430400.00</i>
	G.Total :-	Rs. <u>4577063.00</u> <i>4577063.00</i>
	Or say:-	Rs. <u>4577000.00</u> <i>4577000.00</i>

(RUPEES FORTY FIVE LAKHS SEVENTY SEVEN THOUSAND ONLY)

*[Signature]*  
Asst. Engineer Asst.  
Komna Block

*[Signature]*  
Asst. Executive Engineer  
Komna Block

*[Signature]*  
E.O.  
Komna Block

**Estimator  
Zillaparisad  
Nuapada**

Technical Sanctioned of Rs. 4523000/-  
(Rupees Forty Five Lakhs Twenty Three Thousand)

*[Signature]*  
**Executive Engineer  
Zillaparisad  
Nuapada**

*[Signature]*  
**CDM & PHO cum DMD  
NHM NUAPADA**

Administratively Approved for Rs. 4523000/-  
(Rupees Forty Five Lakhs Twenty Three Thousand only)

*[Signature]*  
**COLLECTOR  
NUAFADA**

## BILL OF QUANTITY

Item of work : Construction of Sub Center Kandetara under Komna Block

Description of items	Unit	Quantity	Rate	Amount
2	3	4	5	6
Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and levelling the bed etc. complete	Cum	175.092	195.38	34209.46
Filling F & P. with sand well watered and rammed etc. complete	Cum	114.957	420.49	48338.18
Providing Cement Concrete( 1:3:6) using 40 mm size hard granite crusher broken metal including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	53.57	4271.82	228831.65
Flyash Brick masonry in cm (1:6) in F&P with costs of materials, conveyance, royalty, taxes etc complete.	Cum	58.9184	3956.93	233135.85
RCC Work of M-20 Grade with 20mm and down graded size HG Chips inc all cost , conveyance and royalty complete.				
<b>Ground Floor</b>				
Column base	Cum	10.0367	4463.93	44803.11
<b>Ground Floor</b>				
Plinth band	Cum	6.87	4824.10	33130.97
<b>Ground Floor</b>				
Column & beam	Cum	3.15	11833.37	37284.68
<b>First Floor</b>				
Column & beam	Cum	3.72	12628.71	46935.72
<b>Ground Floor</b>				
Lintel	Cum	2.88	8067.45	23253.41
<b>First Floor</b>				
Lintel	Cum	2.64	8787.39	23176.26
<b>Ground Floor</b>				
Wall beam	Cum	3.13	11833.37	37028.78
<b>First Floor</b>				
Wall beam	Cum	3.49	12628.71	44014.76
<b>Ground Floor</b>				
Chhaja	Cum	1.81	7717.31	14000.58
<b>First Floor</b>				
Chhaja	Cum	1.77	7907.98	13997.12
<b>Ground Floor</b>				
Roof Slab	Cum	14.47	8705.07	125932.64
<b>First Floor</b>				
Roof Slab	Cum	13.64	9437.84	128766.53
6 Providing Fly ash brick masonry in C.M.(1.6) in superstructure including all cost, convey, royalty etc all complete as per direction of the EIC.	Cum	2.64	3784.33	10000.00
<b>Ground Floor</b>				
	Cum	46.81	3990.26	186801.80
<b>First Floor</b>				
	Cum	38.23	4225.51	161524.31
7 Supplying fitting & fixing M.S.reinforcement including labour charges, cost of rod, T.C. of rod & cost of binding wire etc.all complete as per direction of the EIC.	Qtl			
<b>Ground Floor</b>				
	Qtl	38.11	7295.27	278043.83
<b>First Floor</b>				
	Qtl	21.47	7316.47	157048.15

Description of items	Unit	Quantity	Rate	Amount
2	3	4	5	6
Providing Cement Concrete( 1:2:4) using 12 mm size hard granite crusher broken chips including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	21.6666	5586.06	121030.96
Providing 12 mm thick cement plaster in C.M. (1:6) incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.				
Ground Floor	Sqm	317.92	139.43	44328.46
First Floor	Sqm	191.75	144.30	27669.42
Providing 16 mm thick cement plaster in C.M. (1:6) incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.				
Ground Floor	Sqm	205.13	199.83	40992.84
First Floor	Sqm	219.70	204.18	44857.00
Providing 20 mm thick cement plaster with (1:4) over top of slab incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.				
Ground Floor	Sqm	98.88	219.03	21656.61
First Floor	Sqm	115.97	223.41	25909.01
2 Fixing tiles in floor & dados skirting and rises of steps on 12mm thick bed of cement mortar ( 1 : 1 ) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.				
Ground Floor	Sqm	81.68	971.56	79355.55
First Floor	Sqm	73.36	980.31	71915.98
3 Fixing tiles in floor & dados skirting and rises of steps on 12mm thick bed of cement mortar ( 1 : 3 ) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.				
Ground Floor	Sqm	22.46	1051.51	23620.27
First Floor	Sqm	10.32	1064.67	10982.57
4 Fixing of Ceramic tiles in floor trades and rises of steps and landing on 20mm thick bed of cement mortar ( 1 : 4 ) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.				
Ground Floor	Sqm	7.62	680.12	5181.01
First Floor	Sqm	7.62	688.87	5247.68
15 Fixing of ceramic tiles in dados skirting and rises of steps on 12mm thick bed of cement mortar ( 1 : 3 ) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.				
Ground Floor	Sqm	46.17	737.52	34052.40
First Floor	Sqm	46.17	750.68	34660.03
16 Supplying, fitting, fixing M.S. grill and grill door incl. all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.				
Ground Floor	Kg	898.00	90.90	81628.20
First Floor	Kg	1090.50	90.90	99126.45

SI No	Description of items	Unit	Quantity	Rate	Amount
1	2	3	4	5	6
17	Providing fitting, fixing of Al. door with OELanodized Al. door section of 9202 as verticlemember, 9201 as top meber and 9200 as bottom and middle member and 12 mm thick pre-laminated board fixed on door frame by means of tapered clip No.4660 and the frame to be completed by means of jointing angle No.1855 including all cost of labour, T&P, hire charges of drilling machine, labour charges etc. all complete as per direction of the				
	Ground Floor	Sqm	12.03	4663.62	56105.93
18	Supplying, fitting, fixing fully glazed aluminum framed windows using 15 micorn anodized OEL aluminum section 2082 as out section , 9139 as mullion section, 4124 as a shutter section frame with tapered clip of section 4125, aluminum angle, rubber beading, friction stay and handle etc. with 5 mm black glass etc all complete as per direction of the EIC..				
	Ground Floor	Sqm	15.47	2914.58	45082.24
	First Floor	Sqm	12.40	2914.58	36147.03
19	Painting two coats over one coat of priming of approved shade incl cost of paint, primer & labour etc.all complete as per direction of the EIC.				
	Ground Floor	Sqm	62.24	188.37	11724.71
	First Floor	Sqm	63.36	192.78	12214.49
20	Finishing wall with two coats with weather of approved shade including all cost of material, labour etc. all complete as per direction of the EIC.				
	Ground Floor	Sqm	249.00	73.18	18220.46
	First Floor	Sqm	126.37	74.59	9425.66
21	Providing & Finishing wall surface of wall with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting.				
	Ground Floor	Sqm	722.61	72.98	52736.08
	First Floor	Sqm	722.61	72.98	52736.08
22	plastic emulsion paint two coat to wall with primer of approved shade to give an even shade per 1sgm				
	Ground Floor	Sqm	443.04	81.05	35906.71
	First Floor	Sqm	443.04	82.42	36516.18
23	Stainless Steel Railing				
	Ground Floor	Rft	30.00	550.00	16500.00
	First Floor	Rft	70.00	550.00	38500.00
				Total	3256995.10

*[Signature]*  
29/11/22  
Asst. Engineer  
Komna Block

*[Signature]*  
29/11/22  
Asst Executive Engineer  
Komna Block

*[Signature]*  
30/11/22  
Block Development Office  
Komna Block

*[Signature]*  
29/11/22  
Executive Engineer  
Zillaparisad  
Nuapada

Block Development Office  
Komna



**BILL OF QUANTITY**

Sl No	Description of Items	Unit	Quantity	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and levelling the bed etc.all complete as per direction of the EIC.	Cum	<b>210.3256</b>	195.38	41093.41
2	Filling foundation. & plinth with well graded sand including watering and ramming etc.all complete as per direction of the EIC.	Cum	<b>114.4231</b>	420.49	48113.75
	Providing Cement Concrete( 1:3:6) using 40 mm size hard granite crusher broken metal including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	<b>55.92</b>	4390.26	245511.17
	Providing Flyash in (1:6) C.M. in foundation & plinth including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum			
	(a) Column base	Cum	<b>10.0367</b>	4582.43	45992.47
	b)Plinth band	Cum	<b>16.34</b>	4942.60	80764.84
	(c) Column & beam	Cum	<b>3.15</b>	11951.87	37658.05
	(d) Lintel	Cum	<b>2.88</b>	8185.95	23594.98
	e) Wall beam	Cum	<b>3.13</b>	11951.87	37399.59
	(f) Chhaja	Cum	<b>1.49</b>	7725.01	11483.82
	(g) Roof Slab	Cum	<b>14.47</b>	8823.57	127646.95
5	Providing Fly ash brick masonry in C.M.(1:6) in superstructure including all cost, convey, royalty etc all complete as per direction of the EIC.	Cum	<b>94.17828</b>	4108.39	386921.32
	Supplying fitting & fixing M.S.reinforcement including labour charges, cost of rod, T.C. of rod & cost of binding wire etc.all complete as per direction of the EIC.	Qtl	<b>46.34</b>	1245.32	57712.56
	Providing Cement Concrete( 1:2:4) using 12 mm size hard granite crusher broken chips including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	<b>12.64226</b>	5652.59	71461.51
	Providing 12 mm thick cement plaster in C.M. (1:6) incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Sqm	<b>729.7411</b>	140.62	102614.06
0	Providing 16 mm thick cement plaster in C.M. (1:6) incl all cost,conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Sqm	<b>205.1348</b>	201.25	41283.44
1	Providing 20 mm thick cement plaster with (1:4) over top of slab incl all cost,conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Sqm	<b>98.88</b>	218.72	21626.26
2	Fixing tiles in floor & dados skirting and rises of steps on 12mm thick bed of cement mortar ( 1 : 1 ) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>81.68</b>	985.45	80491.27
3	Fixing tiles in floor & dados skirting and rises of steps on 12mm thick bed of cement mortar ( 1 : 3 ) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>22.46</b>	1052.27	23633.95
	Fixing of Ceramic tiles in floor trades and rises of steps and landing on 20mm thick bed of cement mortar ( 1 : 4) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>7.92</b>	675.35	5348.74

	Fixing of ceramic tiles in dados skirting and rises of steps on 12mm thick bed of cement mortar (1 : 3) joined with neat cement slurry mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc. complete.	Sqm	46.17	736.95	34024.98
14	Supplying, fitting, fixing M.S. grill and grill door incl. all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Kg	898	85.85	77093.30
15	Supplying, fitting, fixing fully glazed aluminum framed windows using 15 micron anodized OEL aluminum section 2082 as out section, 9139 as mullion section, 4124 as a shutter section frame with tapered clip of section 4125, aluminum angle, rubber beading, friction stay and handle etc. with 5 mm black glass etc all complete as per direction of the EIC..		15.47	2914.58	45088.51
16	Providing fitting, fixing of Al. door with OELanodized Al. door section of 9202 as verticle member, 9201 as top member and 9200 as bottom and middle member and 12 mm thick pre-laminated board fixed on door frame by means of tapered clip No.4660 and the frame to be completed by means of jointing angle No.1855 including all cost of labour, T&P, hire charges of drilling machine, labour charges etc. all complete as per direction of the EIC.		12.03	4663.62	56103.37
17	Painting two coats over one coat of priming of approved shade incl cost of paint, primer & labour etc.all complete as per direction of the EIC.	Sqm	62.24	188.37	11723.87
18	Finishing wall with two coats with weather of approved shade including all cost of material, labour etc. all complete as per direction of the EIC.	Sqm	389.00	130.04	50585.11
19	Providing & Finishing wall surface of wall with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting.	Sqm	443.04	72.98	32333.06
20	Paint of approved shade incl all cost of material, labour etc. all complete as per direction of the EIC.	Sqm	443.04	72.98	32333.06
21	Stainless Steel Railing	Rft	70.00	550.00	38500.00
22	Branding of Building as per HWC Norm	Ls			9044.00
25	Dismantling of old Building and throwing of Debris away from the site.				45000.00
26	Barbed Wire fencing all around the building	Ls			119603.00

**Total**      2041784.39

2041784.00

Jr Engineer  
Komna Block

Asst Ex Engineer  
Komna Block

BLD  
Komna Block

Block Development Officer  
Komna

Executive Engineer  
Zillaparisad  
Nuapada

# GENERAL ABSTRACT

Sl. No.	Name of work	Civil cost	EI ( Internal & External )	PH ( Internal & External )	Total amount
		3	4	5	6
1	Const of SC-Samarsingh under Komna Block.	Rs. <del>3125352.00</del> <u>3314468.91</u>	<del>300000.00</del> <u>331446.891</u>	<del>415000.00</del> <u>497170.34</u>	<u>3840357.00</u>
2	Contingency (1%)	Rs. <del>33144.69</del>	0.00	0.00	<u>38404.00</u>
	<b>Total :-</b>	Rs. <u>3347613.60</u>	<u>331446.89</u>	<u>497170.34</u>	<u>3878761.00</u>

GST

~~401713.63~~  
3749327.23

@ 18 %

331446.89

497170.34  
Say

= 698177.00  
~~4577944.36~~  
4577000.00

(RUPEES FORTY FIVE LAKHS SEVENTY SEVEN THOUSAND ONLY)

*[Signature]*  
Junior Engineer  
Komna Block

*[Signature]*  
Asst. Executive Engineer  
Komna Block

*[Signature]*  
Block Development Officer  
Komna Block

*[Signature]*  
**Estimator**  
**Zillaparisad**  
**Nuapada**

*[Signature]*  
26.8.22  
c/s CDM & PHO cum DMD  
NHM NUAPADA

Technically Sanctioned for  
Rs 4577000/- (Rupees Forty five lakhs  
Seventy seven thousand only)

*[Signature]*  
**Executive Engineer**  
**Zillaparisad**  
**Nuapada**

Administratively approved for  
Rs 4577000/- (Rupees Forty five  
lakhs Seventy seven thousand only)

*[Signature]*  
**Collector & DM**  
**NUAPADA**

## BILL OF QUANTITY

Sl No	Description of items	Unit	Quantity	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and levelling the bed etc.all complete as per direction of the EIC.	Cum	<b>156.429</b>	195.38	30563.11
2	Filling foundation. & plinth with well graded sand including watering and ramming etc.all complete as per direction of the EIC.	Cum	<b>103.644</b>	331.61	34369.31
3	Providing Cement Concrete( 1:3:6) using 40 mm size hard granite crusher broken metal including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	<b>45.14</b>	4262.93	192439.25
4	Providing Flyash in (1:6) C.M. in foundation & plinth including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	<b>27.2018</b>	4076.58	110890.27
5	RCC Work of M-20 Grade with 20mm and down graded size HG Chips inc all cost , conveyance and royalty complete.				
	(a) Column base	Cum	<b>10.0367</b>	4423.75	44399.84
	b)Plinth band	Cum	<b>8.48</b>	4779.45	40538.40
	(c) Column & beam	Cum	<b>3.15</b>	11627.81	36636.99
	(d) Lintel	Cum	<b>2.88</b>	7971.79	22977.68
	e) Wall beam	Cum	<b>3.13</b>	11627.81	36385.54
	(f) Chhaja	Cum	<b>1.49</b>	7582.68	11272.23
	(g) Roof Slab	Cum	<b>14.47</b>	8588.71	124249.27
6	Providing Fly ash brick masonry in C.M.(1:6) in superstructure including all cost, convey, royalty etc all complete as per direction of the EIC.	Cum	<b>58.391</b>	4109.91	239981.99
7	Supplying fitting & fixing M.S.reinforcement including labour charges, cost of rod, T.C. of rod & cost of binding wire etc.all complete as per direction of the EIC.	Qtl	<b>39.27</b>	7310.32	287080.91
8	Providing Cement Concrete( 1:2:4) using 12 mm size hard granite crusher broken chips including all cost, conveyance, royalty etc all complete as per direction of the EIC.	Cum	<b>12.6423</b>	5535.73	69984.14
9	Providing 12 mm thick cement plaster in C.M. (1:6) incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Sqm	<b>418.573</b>	140.69	58890.51
10	Providing 16 mm thick cement plaster in C.M. (1:6) incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Sqm	<b>205.135</b>	201.34	41302.46
11	Providing 20 mm thick cement plaster with (1:4) over top of slab incl all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Sqm	<b>98.88</b>	218.39	21593.90

12	Fixing vetrified tiles in floor & dados skirting and rises of steps on 20mm thick bed of cement mortar (1:4) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>81.68</b>	1000.01	81679.13
13	Fixing of verified tiles in dados skirting and rises of steps on 12mm thick bed of cement mortar (1:3) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>22.46</b>	1054.46	23686.55
	Fixing of Ceramic tiles in floor trades and rises of steps and landing on 20mm thick bed of cement mortar (1:4) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>7.62</b>	699.24	5326.65
	Fixing of ceramic tiles in dados skirting and rises of steps on 12mm thick bed of cement mortar (1:3) joined with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles & rubbing and polishing etc.complete.	Sqm	<b>46.17</b>	739.81	34157.87
14	Supplying, fitting, fixing M.S. grill and grill door incl. all cost, conveyance, royalty of material, labour etc all complete as per direction of the EIC.	Kg	<b>898</b>	85.85	77093.30
15	Supplying, fitting, fixing fully glazed aluminum framed windows using 15 micorn anodized OEL aluminum section 2082 as out section, 9139 as mullion section, 4124 as a shutter section frame with tapered clip of section 4125, aluminum angle, rubber beading, friction stay and handle etc. with 5 mm black glass etc all complete as per direction of the EIC		<b>15.47</b>	2914.58	45082.24
16	Providing fitting, fixing of Al. door with OELanodized Al. door section of 9202 as verticle member, 9201 as top meber and 9200 as bottom and middle member and 12 mm thick pre-laminated board fixed on door frame by means of tapered clip No.4660 and the frame to be completed by means of jointing angle No.1855 including all cost of labour, T&P, hire charges of drilling machine, labour charges etc. all complete as per direction of the EIC		<b>12.03</b>	4663.62	56105.93
17	Painting two coats over one coat of priming of approved shade incl cost of paint, primer & labour etc.all complete as per direction of the EIC.	Sqm	<b>62.24</b>	188.37	11724.71
18	Finishing wall with two coats with weather of approved shade including all cost of material, labour etc. all complete as per direction of the EIC.	Sqm	<b>305.34</b>	130.04	39706.37
19	Providing & Finishing wall surface of wall with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive	Sqm	<b>443.04</b>	72.98	32332.91
20	Paint of approved shade incl all cost of material, labour etc. all complete as per direction of the EIC.	Sqm	<b>443.04</b>	72.98	32332.91
21	Stainless Steel Railing	Rft	<b>30.00</b>	550.00	16500.00
22	Branding of Building as per HWC Norm	Ls			8500.00

25	Dismantaling of old Building and throwing of Debris away from the site				30000.00
26	Barbed Wire fencing all around the building	18			30000.00
<b>Total</b>					<b>1927784.36</b>

*[Signature]*  
 Junior Engineer  
 Komna Block

*[Signature]* 19/02/22  
 Asst Executive Engineer  
 Komna Block

*[Signature]*  
 Block Development Officer  
 Komna Block  
**Block Development Officer**  
**Komna**

*[Signature]*  
**Executive Engineer**  
**Zilaparised**  
**Nuapada**